



PROVIDENCE WATER
WATER MAIN REPLACEMENT/REHABILITATION (WMR) PROGRAM
2016 Edgewood Neighborhood, Cranston

Scope: Systematic replacement and/or rehabilitation of (undersized) 6", 8", and 12" unlined, 100 year old cast iron water mains.

Reason: To resolve historic, tracked water quality issues from customers, such as discolored water and low pressure. Also, to rehab water mains in advance of roadway pavement upgrades by City or State.

Schedule: An April 2016 start of Cleaning & Cement Lining, Replacement, and Tie-ins of existing water mains for the 2016 construction season. Temporary surface restoration to be followed by Permanent surface restorations after a 60 day settlement period.

FAQs:

Clean & Cement Line -	11,000 LF
Replacement -	8,700 LF

Streets (Cleaning & Cement Lining of Existing Water Mains):

Cranston - Edgewood Area (Primary Roads): Narragansett Blvd (from Norwood Ave to Strathmore Rd)

Cranston - Edgewood Area (Secondary Roads): Kneeland St, Tucker Ave, Parkway Ave, Commercial St, Sheldon St, George St, Springwood St, Aborn St, and Marcy St

Various Locations: Small Water Main Replacements or short Water Main Tie-ins

Streets (Replacement of Existing Water Mains):

Cranston - Edgewood Area (Secondary Roads): Shaw Ave, Columbia Ave, Albert Ave, Arnold Ave, and Pawtuxet Ave (from Norwood Ave to Arnold Ave)

Various Locations: Small Water Main Replacements or short Water Main Tie-ins

Streets (Tie-in Existing Water Mains):

Cranston - Edgewood Area (Primary Roads): Broad St (from Park Ave to George St)

Various Locations: Small Water Main Replacements or short Water Main Tie-ins

Operations: Install surface water bypass piping, connect businesses/homes to bypass piping, excavate access pits, clean & cement line existing water mains, install new ductile iron water main where necessary, install new valves and hydrants, replace any encountered lead water services (replace homeowner lead service if requested), disinfect newly lined and new mains and appurtenances, backfill access pits and activate newly lined water main, install temporary pavement, disconnect and remove bypass piping, install permanent pavement (after 60 day settlement period).

Hotline - 877-797-2267
After Hours - 401-952-6535

Website - www.provwater.com
Email - wmr@provwater.com